

*If you are using a printed copy of this procedure, and not the on-screen version, then you **MUST** make sure the dates at the bottom of the printed copy and the on-screen version match. The on-screen version of the Collider-Accelerator Department Procedure is the Official Version. Hard copies of all signed, official, C-A Operating Procedures are kept on file in the C-A ESHQ Training Office, Bldg. 911A.*

C-A OPERATIONS PROCEDURES MANUAL

4.120.81.a Tandem Critical Device Tests

Attachment

C-A-OPM Procedures in which this Attachment is used.		
4.120.81		

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____

Approved: Signature on File _____
 Collider-Accelerator Department Chairman Date

V. Castillo

PASS SEMI-ANNUAL ACCEPTANCE TEST PROTOCOL

Division A Software Filename and Checksum: Title: _____ Checksum: _____

Division B Software Filename and Checksum: Title: _____ Checksum: _____

Initial testing complete:

Test Team Leader's Name (Print): _____ Life Number: _____

Test Team Leader's Name (Sign): _____ Date: ____/____/____

Acceptance test procedure complete (following repairs and retesting if required):

Test Team Leader's Name (Print): _____ Life Number: _____

Test Team Leader's Name (Sign): _____ Date: ____/____/____

Test results reviewed by:

Safety Section Head's Name (Print): _____ Life Number: _____

Safety Section Head's Name (Sign): _____ Date: ____/____/____

Test results accepted by Radiation Safety Committee:

RSC Member's Name (Print): _____ Life Number: _____

RSC Member's Name (Sign): _____ Date: ____/____/____

1.1 Test of Beam Plugs in Target Room 2

- ☐ **VERIFY** Tandem Control Room (TCR) sees **Target Room 2 Beam Stops (TR2 BS)** Div A ☐ and Div B ☐

INSERTED

- PLACE** **Beam Plug Tester (BPT)** on any Beam Plug [BP #_____]]
EXTRACT **BP#** ____

- ☐ **VERIFY** **BP#** ____

EXTRACTED

- ☐ **VERIFY** TCR sees **TR2 BS** Div A ☐ and Div B ☐

EXTRACTED

- INSERT** **BP#** ____

- ☐ **VERIFY** TCR sees **TR2 BS** Div A ☐ and Div B ☐

INSERTED

- REMOVE** **BPT** from **BP#** ____

- ☐ **Check for acceptance of Test of Beam Plugs in Target Room 2**

1.2 Test of Beam Plugs in Target Room 3

- ☐ **VERIFY** Tandem Control Room (TCR) sees **Target Room 3 Beam Stops (TR3 BS)** Div A ☐ and Div B ☐

INSERTED

- PLACE** **Beam Plug Tester (BPT)** on any Beam Plug [BP #_____]]
EXTRACT **BP#** ____

- ☐ **VERIFY** **BP#** ____

EXTRACTED

- ☐ **VERIFY** TCR sees **TR3 BS** Div A ☐ and Div B ☐

EXTRACTED

- INSERT** **BP#** ____

- ☐ **VERIFY** TCR sees **TR3 BS** Div A ☐ and Div B ☐

INSERTED

- REMOVE** **BPT** from **BP#** ____

- ☐ **Check for acceptance of Test of Beam Plugs in Target Room 3**

1.3 Test of Beam Plugs in Target Room 4

- ☐ **VERIFY** Tandem Control Room (TCR) sees **Target Room 4 Beam Stops (TR4 BS)** Div A ☐ and Div B ☐

INSERTED

- PLACE** **Beam Plug Tester (BPT)** on any Beam Plug [BP #_____]]
EXTRACT **BP#** ____

- ☐ **VERIFY** **BP#** ____

EXTRACTED

- ☐ **VERIFY** TCR sees **TR4 BS** Div A ☐ and Div B ☐

EXTRACTED

- INSERT** **BP#** ____

- ☐ **VERIFY** TCR sees **TR4 BS** Div A ☐ and Div B ☐

INSERTED

- REMOVE** **BPT** from **BP#** ____

- ☐ **Check for acceptance of Test of Beam Plugs in Target Room 4**

1.4 Test of MP6 and MP7 Beam Stops (BS)

<input type="checkbox"/>	VERIFY	MP6 BS is	CLOSED
<input type="checkbox"/>	VERIFY	TCR sees MP6 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	CLOSED
<input type="checkbox"/>	VERIFY	MP7 BS is	CLOSED
<input type="checkbox"/>	VERIFY	TCR sees MP7 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	CLOSED
<input type="checkbox"/>	SHORT	Terminals: KA15 [1,2]; KA15 [5,6]; KB15 [3,4]; KB15 [7,8]	
<input type="checkbox"/>	VERIFY	Terminals: KA15 [1,2] <input type="checkbox"/>; KA15 [5,6] <input type="checkbox"/>; KB15 [3,4] <input type="checkbox"/>; KB15 [7,8] <input type="checkbox"/> are	SHORTED
<input type="checkbox"/>	SHORT	Terminals: KA15 [3,4]; KA15 [7,8]; KB15 [1,2]; KB15 [3,4]	
<input type="checkbox"/>	VERIFY	Terminals: KA15 [3,4] <input type="checkbox"/>; KA15 [7,8] <input type="checkbox"/>; KB15 [1,2] <input type="checkbox"/>; KB15 [3,4] <input type="checkbox"/> are	SHORTED
<input type="checkbox"/>	VERIFY	TCR sees Interlock Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	O.K.
<input type="checkbox"/>	SHORT	Terminals: KA40 [13,14]; KA41 [13,14]	
<input type="checkbox"/>	VERIFY	Terminals: KA40 [13,14] <input type="checkbox"/>; KA41 [13,14] <input type="checkbox"/> are	SHORTED
<input type="checkbox"/>	SHORT	Terminals: KB40 [13,14]; KB41 [13,14]	
<input type="checkbox"/>	VERIFY	Terminals: KB40 [13,14] <input type="checkbox"/>; KB41 [13,14] <input type="checkbox"/> are	SHORTED
<input type="checkbox"/>	VERIFY	TCR sees MP6 Interlock Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	O.K.
<input type="checkbox"/>	VERIFY	TCR sees MP7 Interlock Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	O.K.
	OPEN	MP6 and MP7 BS at Tandem Control Room (TCR)	
<input type="checkbox"/>	VERIFY	TCR sees MP6 Reach Back Timer Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	ENABLED
<input type="checkbox"/>	VERIFY	TCR sees MP7 Reach Back Timer Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	ENABLED
<input type="checkbox"/>	VERIFY	MP6 BS is	OPEN
<input type="checkbox"/>	VERIFY	TCR sees MP6 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	OPEN
<input type="checkbox"/>	VERIFY	MP7 BS is	OPEN
<input type="checkbox"/>	VERIFY	TCR sees MP7 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	OPEN
<input type="checkbox"/>	CLOSE	MP6 BS	
<input type="checkbox"/>	VERIFY	MP6 BS is	CLOSED
<input type="checkbox"/>	VERIFY	TCR sees MP6 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	CLOSED
<input type="checkbox"/>	CLOSE	MP7 BS	
<input type="checkbox"/>	VERIFY	MP7 BS is	CLOSED
<input type="checkbox"/>	VERIFY	TCR sees MP7 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/>	CLOSED
<input type="checkbox"/>	REMOVE	Shorts from Terminals: KA15 [1,2]; KA15 [5,6]; KB15 [3,4]; KB15 [7,8]	
<input type="checkbox"/>	VERIFY	Terminals: KA15 [1,2] <input type="checkbox"/>; KA15 [5,6] <input type="checkbox"/>; KB15 [3,4] <input type="checkbox"/>; KB15 [7,8] <input type="checkbox"/> are	OPEN

	REMOVE	Shorts from Terminals: KA15 [3,4]; KA15 [7,8]; KB15 [1,2]; KB15 [3,4]	
<input type="checkbox"/>	VERIFY	Terminals: KA15 [3,4] □; KA15 [7,8] □; KB15 [1,2] □; KB15 [3,4] □ are	OPEN
<input type="checkbox"/>	VERIFY	TCR sees Interlock Div A □ and Div B □	FAIL
	SET	Key Bypass switch to	BYPASS
<input type="checkbox"/>	VERIFY	Key Bypass switch is set to	BYPASS
<input type="checkbox"/>	VERIFY	TCR sees Interlock Div A □ and Div B □	FAIL
	OPEN	MP6 and MP7 BS at Tandem Control Room (TCR)	
<input type="checkbox"/>	VERIFY	TCR sees MP6 Reach Back Timer Div A □ and Div B □	ENABLED
<input type="checkbox"/>	VERIFY	TCR sees MP7 Reach Back Timer Div A □ and Div B □	ENABLED
<input type="checkbox"/>	VERIFY	MP6 BS is	OPEN
<input type="checkbox"/>	VERIFY	TCR sees MP6 BS Div A □ and Div B □	OPEN
<input type="checkbox"/>	VERIFY	MP7 BS is	OPEN
<input type="checkbox"/>	VERIFY	TCR sees MP7 BS Div A □ and Div B □	OPEN
	CLOSE	MP6 BS	
<input type="checkbox"/>	VERIFY	TCR sees MP6 BS Div A □ and Div B □	CLOSED
	CLOSE	MP7 BS	
<input type="checkbox"/>	VERIFY	TCR sees MP7 BS Div A □ and Div B □	CLOSED
	SET	Key Bypass switch to	OFF
<input type="checkbox"/>	VERIFY	Key Bypass switch is set to	OFF
<input type="checkbox"/>	Check for acceptance of Test of MP6 and MP7 Beam Stops		

1.5 Test of Reachback

	OPEN	MP6 and MP7 BS at Tandem Control Room (TCR)	
<input type="checkbox"/>	VERIFY	TCR sees MP6 BS Div A □ and Div B □	OPEN
<input type="checkbox"/>	VERIFY	TCR sees MP7 BS Div A □ and Div B □	OPEN
	OPEN	Fuses F10 and F11	
<input type="checkbox"/>	VERIFY	Fuses F10 and F11 are	OPEN
	CLOSE	MP6 and MP7 BS at TCR	
<input type="checkbox"/>	VERIFY	MP6 BS is	CLOSED
<input type="checkbox"/>	VERIFY	TCR sees MP6 BS Div A □ and Div B □	OPEN
<input type="checkbox"/>	VERIFY	MP7 BS is	CLOSED
<input type="checkbox"/>	VERIFY	TCR sees MP7 BS Div A □ and Div B □	OPEN

- | | | | |
|--------------------------|--|--|-----------------|
| <input type="checkbox"/> | VERIFY | TCR sees MP6 Reachback | ENABLED |
| <input type="checkbox"/> | VERIFY | At MP6 NII Preaccel PS Interlock | ON |
|
 | | | |
| <input type="checkbox"/> | VERIFY | TCR sees MP7 Reachback | ENABLED |
| <input type="checkbox"/> | VERIFY | At MP7 NII Preaccel PS Interlock | ON |
|
 | | | |
| <input type="checkbox"/> | CLOSE | Fuses F10 and F11 | |
| <input type="checkbox"/> | VERIFY | Fuses F10 and F11 are | CLOSED |
|
 | | | |
| <input type="checkbox"/> | VERIFY | MP6 BS is | CLOSED |
| <input type="checkbox"/> | VERIFY | TCR sees MP6 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/> | CLOSED |
| <input type="checkbox"/> | VERIFY | TCR sees MP6 Reachback | DISABLED |
| <input type="checkbox"/> | VERIFY | At MP6 NII Preaccel PS Interlock | OFF |
|
 | | | |
| <input type="checkbox"/> | VERIFY | MP7 BS is | CLOSED |
| <input type="checkbox"/> | VERIFY | TCR sees MP7 BS Div A <input type="checkbox"/> and Div B <input type="checkbox"/> | CLOSED |
| <input type="checkbox"/> | VERIFY | TCR sees MP7 Reachback | DISABLED |
| <input type="checkbox"/> | VERIFY | At MP7 NII Preaccel PS Interlock | OFF |
|
 | | | |
| <input type="checkbox"/> | Check for acceptance of Test of MP6 and MP7 Reachback | | |

1.6 Test of 12MW040 IN

- | | | | |
|--------------------------|---|---|-----------------|
| <input type="checkbox"/> | VERIFY | 12MW040 is | OUT |
| <input type="checkbox"/> | VERIFY | TCR sees 12MW040 | OUT |
|
 | | | |
| | INSERT | 12MW040 at Tandem Control Room (TCR) | |
|
 | | | |
| <input type="checkbox"/> | VERIFY | 12MW040 is | INSERTED |
| <input type="checkbox"/> | VERIFY | TCR sees 12MW040 | INSERTED |
|
 | | | |
| | EXTRACT | 12MW040 at Tandem Control Room (TCR) | |
|
 | | | |
| <input type="checkbox"/> | VERIFY | TCR sees 12MW040 | OUT |
|
 | | | |
| <input type="checkbox"/> | Check for acceptance of Test of 12MW040 IN | | |

1.7 Test of Div A RIS Unit for Power Supply A and Div B RIS Unit for Power Supply E

- | | | | |
|--------------------------|--|---|-----------------|
| <input type="checkbox"/> | SET | Div A RIS unit for Power Supply A above | SETPOINT |
| <input type="checkbox"/> | VERIFY | Div A RIS unit is above | SETPOINT |
| <input type="checkbox"/> | VERIFY | TCR sees RIS Comp Div A | FAIL |
| | | | |
| <input type="checkbox"/> | SET | Div A RIS unit below | SETPOINT |
| <input type="checkbox"/> | VERIFY | Div A RIS unit is below | SETPOINT |
| <input type="checkbox"/> | VERIFY | TCR sees RIS Comp Div A | O.K. |
| | | | |
| <input type="checkbox"/> | SET | Div A RIS unit at | SETPOINT |
| <input type="checkbox"/> | VERIFY | Div A RIS unit at | SETPOINT |
| <input type="checkbox"/> | VERIFY | TCR sees RIS Comp Div A | O.K. |
| | | | |
| <input type="checkbox"/> | SET | Div B RIS unit for Power Supply E above | SETPOINT |
| <input type="checkbox"/> | VERIFY | Div B RIS unit is above | SETPOINT |
| <input type="checkbox"/> | VERIFY | TCR sees RIS Comp Div B | FAIL |
| | | | |
| <input type="checkbox"/> | SET | Div B RIS unit below | SETPOINT |
| <input type="checkbox"/> | VERIFY | Div B RIS unit is below | SETPOINT |
| <input type="checkbox"/> | VERIFY | TCR sees RIS Comp Div B | O.K. |
| | | | |
| <input type="checkbox"/> | SET | Div B RIS unit at | SETPOINT |
| <input type="checkbox"/> | VERIFY | Div B RIS unit at | SETPOINT |
| <input type="checkbox"/> | VERIFY | TCR sees RIS Comp Div B | O.K. |
| | | | |
| <input type="checkbox"/> | VERIFY | TCR sees RIS Comp Div A <input type="checkbox"/> and RIS Comp Div B <input type="checkbox"/> | O.K. |
| | | | |
| <input type="checkbox"/> | Check for acceptance of Test of Div A RIS Unit for Power Supply A and Div B RIS Unit for Power Supply E | | |

END OF TEST PROCEDURE

TTL: Sign for completion of initial testing: _____

Date: ____/____/____

TTL: Sign for completion of final testing: _____

Date: ____/____/____