If you are using a printed copy of this procedure, and not the on-screen version, then you <u>MUST</u> make sure the dates at the bottom of the printed copy and the on-screen version match.

The on-screen version of the Collider-Accelerator Department Procedure is the Official Version.

Hard copies of all signed, official, C-A Operating Procedures are kept on file in the C-A ESHQ

Training Office, Bldg. 911A.

C-A OPERATIONS PROCEDURES MANUAL

$\overline{}$	1	10	D 4.	CII / F 1	1 D / 2 D
/		IΧ	Kegeneration	of Heat Exchanger	IB//B
, .		. 1 0	1 to Scholation	of front Entitlement	10/20

Text Pages 2 through 5

Hand Processed Changes

Date

Page Nos.

Initials

· · · · · · · · · · · · · · · · · · ·		
A 1	C	
Annroved:	Signature on File	
ripproved	Signature on 1 tte	
		D .
	Collider-Accelerator Department Chairman	Date
	Comaci riccolorator Department Chamman	Date

D. Lederle

HPC No.

7.1.18 Regeneration of Heat Exchanger 1B/2B

1. Purpose

This procedure provides instructions for regenerating heat exchanger 1B/2B on the RHIC 25 kW Helium Refrigerator. This procedure shall be performed when heat exchanger 1B/2B is contaminated and has been taken offline. The steps necessary to take heat exchanger 1B/2B offline are not covered under this procedure, please reference C-A OPM 7.1.15.

2. Responsibilities

- 2.1 The shift supervisor or an operator designated by the shift supervisor is responsible for conducting the procedure and providing documentation in the Cryogenic Control Room Log.
- 2.2 Should a problem arise in the process of regenerating the heat exchanger, the shift supervisor shall report to the technical supervisor for instructions before continuing.

3. <u>Prerequisites</u>

- 3.1 Operator shall be familiar with the refrigerator P&ID drawing 3A995009, the physical location of components on the refrigerator, and the refrigerator control pages found on the CRISP control system.
- 3.2 The regeneration skid must be available for use.
- 3.3 Oxygen monitor and hygrometer in compressor room are set to read compressor discharge.

4. <u>Precautions</u>

4.1 If there is liquid helium in the refrigerator pots, all personnel entering the refrigeration wing of 1005R must be ODH Class 1 qualified have a Personal Oxygen Monitor (POM) and carry an emergency escape pack, if the refrigerator is operating.

 5.1	Date
 5.2	The following valves shall be set to the CLOSED position:
	Process Valves:
	H714A H716M H724M H715M H717M H713M
	Valves to atmosphere, relief valve header, vacuum, or pure helium
	H719M H856M H9200M H721M H857M H9195M H723M H1102A H706M H848M H9198M H305M
	H855MH9199M
 5.3	Ensure the following valves are OPEN:
	Process Valves:
	H822M
 5.4	Start the regeneration (regen) skid per <u>C-A-OPM 7.1.36</u> , "Regeneration System Normal Operation".
 5.5	Open the following valves:
	H9107M H722M H9108M H9110M H9109M H847M H718M H9106M H720M H705M
 5.6	Close regen manifold bypass valve H9100M.
 5.7	Turn on regen skid pre-heater.
 5.8	Monitor sensors TI708, TI709, TI710, TI711, TI868, TI869, TI870, TI251, TI252, and TI253.
 5.9	When the above sensors reach 310°K, continue to regenerate for a least 1 hour. Hygrometer reading must be -30°C to -40°C and improving less than 0.5°C/hr.

 5.10	Turn off regen skid preheater.
 5.11	Open valve H9100M.
 5.12	Close the following valves:
	H705M H722M H847M H9107M H9110M H9108M H718M H9109M H720M
 5.13	Secure the regeneration skid per <u>C-A-OPM 7.1.36</u> .
 5.14	Introduce pure helium into heat exchanger 1B/2B by cracking open valve H706M Immediately crack open the following valves to purge heat exchanger 1B/2B:
	H719M H855M H721M H856M H723M H857M
 5.15	Adjust valves in previous step as necessary until an audible purge is heard.
 5.16	Allow heat exchanger 1B/2B to purge for 30 minutes at an audible level.
 5.17	Close the following valves:
	H719M H855M H721M H856M H723M H857M
 5.18	When PI844H reaches approximately 250 PSIA, close valves H706M and H9106M
 5.19	Open valves H715M, H716M and H717M as a sign that heat exchanger 1B/2B has been regenerated and is ready for service.

6. **Documentation**

- 6.1 The check-off lines on the procedure are for place-keeping only. The procedure is not to be initialed or signed, it is not a record.
- 6.2 The Shift Supervisor, or designee, shall document the completion of the procedure in the Cryogenics Control Room Log.

7. References

- 7.1 Drawing 3A995009, 25KW Helium Refrigerator P&ID.
- 7.2 <u>C-A-OPM 7.1.15</u>, "Heat Exchanger 1A/2A Online and Heat Exchanger 1B/2B Offline".
- 7.3 <u>C-A-OPM 7.1.36</u>, "Regeneration System Normal Operation".

8. Attachments

8.1 None