E-cooling Experiment High Beta Cavity & Cryomodule BNL 703.75 MHz Superconducting Linac Development

A. Burger
Manufacturing Program Manager

Final Design Review

@

Brookhaven National Laboratory 7/22/04

This work prepared for Brookhaven National Laboratory under Contract
Number 70819



Outline

- Introduction
- Accomplishments Phase I
- Technical Approach Second

Year

•Manufacturing Schedule

Assessment -Top Level Phase II



Introduction

The Final Design Review (FDR) is a major milestone of the e-Cooling Experiment Technology Development Phase and will address the mechanical design and analytical progress on the elliptical cavity, helium vessel and cryomodule components. It was a combined effort between Brookhaven Laboratory and AES and utilized a multi-disciplined philosophy comprised of engineering design, RF / FEA analysis and manufacturing producibility.



Accomplishments Phase I

- -Completed Mechanical Design and FEA of 5 cell RF Cavity, He Vessel, Power Coupler, & Cryostat
- -Interfaces to external piping for both cold and warm connections defined
- -Instrumentation type, locations and method of installation well defined
- -Manufacturing Plan and Production Readiness approved and Manufacturing drawings required for niobium fabrication in process
- -Manufacturing forming, assembly and tuning fixtures for cavity are complete
- -Engineering Design, Manufacture and Testing @ AES nearing completion on two (5) cell copper cold models
 - . Adjustable HOM filter position and orientation for testing versatility
 - . Completed manufacturing drawing package delivered to BNL
- -All Government Furnished niobium and niobium titanium has been received at the AES facility and a Certificate of Compliance has been provided to BNL



TECHNICAL APPROACH - PHASE II SECOND YEARS WORK

- Fabrication of niobium Cavity and associated components, He Vessel, Cryostat, Magnetic / Thermal Shielding and Support Structure.
- . All niobium end/mid half cells plus spares have been hydroformed
- Chemical Processing and Test @ Jefferson Laboratory.
- -Return tested cavity to AES for tuning and welding of Helium Vessel
- -Final Processing @ JLAB During APRIL, 2005
- Integration and Test of SRF Cryomodule at BNL begins MAY, 2005.
- -All Engineering Design And Manufacturing skills in place.



										PRO	ODU	СТІ	ON	& TE	EST									
Activity		2003					2004													2005				
Name	J	Α	S	0	N	D	J	F	М	Α	М	J	J	Α	S	0	N	D	J	F	M	Α	М	J
Project	Cor	ntract							Prelin	ninary			Final	Desigr	Revi	ew				Start	Cavity		Begin	ıRF
Milestones	Award							Design Review			iew (F		_						Process at JLAB			LAB		at BNL
_																								
Construction of (5) Cell																								
Super Conducting												דמוני	ΓASK											
Cavity and SRF												OUDI	ASK											
Cryomodule																								
Fabrication of (5) Cell																								
Cavity and Helium Vessel													[
Fabrication of Power																								
Coupler and Tuner																								
(Procurement FPC)																								
Fabrication of Cryostat &																								
Associated Structure																								
Package, Shipping and																								
Delivery of Cavity																								
Chemical Processing and																								
Test of Cavity at Jefferson																				_	l			
Deliver Tested (5) Cell																								
 Cavity to AES for Tuning 																						1		
and Weld of Helium Vesse	ı																					•		
 Deliver Cavity to JLAB for 																								
Final Processing																								
Deliver Cavity to BNL																							V	
,							-							-								-		
Assembly and																								
Integration of SRF											5	SUBT	TASK											
Cryomodule																								
Assemble Cryomodule at																								
BNL Supported by AES																								
Begin RF Testing of																								
Cryomodule																								4
c., 3110 aaio																								

