If you are using a printed copy of this procedure, and not the on-screen version, then you <u>MUST</u> make sure the dates at the bottom of the printed copy and the on-screen version match.

The on-screen version of the Collider-Accelerator Department Procedure is the Official Version.

Hard copies of all signed, official, C-A Operating Procedures are kept on file in the C-A ESHQ

Training Office, Bldg. 911A.

C-A OPERATIONS PROCEDURES MANUAL

ATTACHMENT

4.56.d Northwest Corner of the Target Building Sweep Checklist

C-A-0	OPM Procedures in w	hich this Attachment i	s used.	
4.56				
	<u>Hand Pro</u>	cessed Changes		
HPC No.	<u>Date</u>	Page Nos.	<u>Initials</u>	
	Approved:Co	Signature on File llider-Accelerator Department	artment Chairman	D
Ingrassia				

NORTHWEST CORNER OF THE TARGET BUILDING SWEEP CHECKLIST

(Team Le	eader)(Operator 2)
Time:	Date:
be comp if the s	Warning: Decrease the encountered during the sweep, THEN determine whether their work will pleted in a short time. IF the work will take a long time, THEN contact the OC to see weep should be aborted. IF the work will be completed in a short time, THEN write the encountered of the checklist and verify that they leave the enclosure.
<u>Prerequis</u>	<u>ites</u>
Keys, C-A-C CHEC	Operators to perform the sweep AA256A, Fan-house keys OPM-ATT 4.56.d "NORTHWEST CORNER OF THE TARGET BUILDING SWEEP CKLIST" (1 page) beam stops 1 & 2 are closed (see MCR_2-2G7, G8)
1.	Team Leader and Operator go to the door at the Northwest corner of the Target Building.
2.	Team Leader unlocks the door.
3.	Operator 2 stands static watch inside the door.
4.	Team Leader verifies that the Health Physics gate adjacent to the door is pad-locked. IF the gate is not padlocked THEN abort the sweep AND contact HP to sweep the storage area.
5.	Team Leader goes to the north end of the area (farthest from the door).
6.	Team Leader sweeps back to the door and re-joins Operator 2.
7.	Both Operators sweep out the door.
8.	Team Leader padlocks the door.
9.	Team Leader informs OC that NW corner of the Target Building is swept and secured for beam.
10.	After verifying that all of the required information is filled out, Team Leader files the checklist in Completed Sweep Checklist Binder and stores the keys in the Captured Key Locker above MCR 2