

*If you are using a printed copy of this procedure, and not the on-screen version, then you **MUST** make sure the dates at the bottom of the printed copy and the on-screen version match.  
The on-screen version of the Collider-Accelerator Department Procedure is the Official Version.  
Hard copies of all signed, official, C-A Operating Procedures are kept on file in the C-A ESHQ Training Office, Bldg. 911A.*

## C-A OPERATIONS PROCEDURES MANUAL

### 11.4.4 Procedure for Exciting the STAR Magnet

Text Pages 2 through 3

#### Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approved: \_\_\_\_\_  
Collider-Accelerator Department Chairman      Date

K. Foley

#### **11.4.4 Procedure for Exciting the STAR Magnet**

##### **1. Purpose**

The purpose of this procedure is to turn on and ramp the STAR Magnet to the desired field.

##### **2. Responsibilities**

The Star Magnet Operator is responsible for conducting the procedure.

##### **3. Prerequisites**

- 3.1 A STAR Magnet Coordinator shall have completed the requirements of [C-A OPM 11.4.2, "Procedure for Preparing the STAR Magnet for Operation."](#)

##### **4. Precautions**

None

##### **5. Procedure**

- 5.1 The STAR Magnet Operator shall call the main control room to ask for approval to excite or change the settings of the STAR magnet. The level of power should be given, namely 4MW for full field or 1MW for half field. If deemed necessary by MCR, changes will only be made between RHIC beam abort and refill.
- 5.2 The STAR Magnet Operator shall then use the STAR Magnet Control Page to set the magnetic field. The current set points in amps are shown in the table below.

	Half Field	Full Field	Approx. PS Limit
Main PS	2250	4500	5000
Space trim PS's (2)	300	575	600
Pole Tip PS's (2)	665	1330	1400

**6.    Documentation**

None

**7.    References**

None

**8.    Attachments**

None